



No. LGSD-II / AC- 24 / 2012 – 13/
Government of India
Central Water Commission
Lower Godavari Sub Division No-II



Phone: 0883 2468753
FAX: 0883 2468753

Opp. RTC Bus Complex,
Danavaiah Pet Post.
Rajahmundry -533 103.

Email: aecwc_rjy@yahoo.com

Date: .11.2012

NOTICE INVITING QUOTATIONS

**SUB: Quotation for the work of restoration of Telemetry Bubbler line at site Koida (V),
Velarupadu Mandal, Khammam District.**

Sir(s)

Sealed quotations are invited for the work of Restoration of Telemetry Bubbler line at site Koida, so as to reach this office by 15.00 hrs on 22.12.2012. The quotations will be opened by the undersigned on the same day at 16.00 hrs. Intended bidders or their authorized representative may present at the time of opening of quotation, if they wish so.

Sl.No.	Description of work	QTY.	RATE	UNIT	AMOUNT
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus soil as directed within a lead of 50m- All kinds of soil. (code2.8.1) For Bubbler line checking For Termination block Net Quantity	24.000		Cum	
2	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc. (external work) (code18.12.5) For damaged portion of Bubbler line	36.000		m	
3	Providing and fixing G.I. Union in G.I. pipe including cutting and threading the pipe and making long screws etc. complete (new work) (code18.46.5) For damaged portion of Bubbler line	4 Nos.		Each	
4	Providing I-Section of 1.50m length at the Termination block for better support to Bubbler line	1 Nos.		L.S.	
5	Centering and shuttering including strutting, propping etc. and removal of form work for Foundations, footings, bases of Columns (Code: 4.3.1) For Termination block	1.200		Sqm	

6	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work upto plinth level 1:2:4 (1 Cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) (Code: 4.2.3)	0.900		Cum	
7	Re fitting charges of the checked G.I.bubbler line	160.000		L.S.	
8	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth: consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m (code: 2.25)	23.400		Cum	
GRAND TOTAL					

Terms & Conditions:

1. The sealed envelope contained quotations should be super scribed as "**Quotations for work of restoration of Telemetry Bubbler line at site Koida**" due for opening on 22.12.2012 at 1600 hrs
2. The work will be executed/inspected by the departmental officer in all stages.
3. The Security Deposit of 10% may be deducted from the Bill and will be released after six months completion of the work satisfactorily. Any damage/penalty to the Govt. property it will be adjusted from the security deposit.
4. 2% Income tax & other taxes as applicable shall be deducted from the total amount.
5. Rates should be mentioned, inclusive of all taxes, levies, transportation, loading, unloading, and stacking of materials and providing necessary labour, materials, equipment, etc.
6. The rates quoted should be valid at least for a period of six months from the date of opening of the quotation.
7. No T&P materials for any work including scaffolding/shuttering etc, will be provided by this department for the above said works.
8. The curing of the cement works should be done as per the standards by the contractor.
9. After satisfactory completion of the works in all respects, the bill in triplicate may be submitted for payment to the undersigned.
10. The payment will be made generally by Demand draft on SBI after completion of work satisfactorily and on submission of bill in triplicate.
11. However payment will be made on actual measurements only.
12. This office reserves the right to reject any one or all quotations without assigning any reasons there of.

Sub-Divisional Engineer

To
M/s.

Copy for information to:-

1. The Superintending Engineer, Godavari Circle, CWC, Hyderabad along with soft copy for uploading the same in CPP.
2. The Executive Engineer, LGD, CWC, Hyderabad, w.r.t Lr. No. LGD/DB/Estimate/2012-13/2188 - 91, dated 25.07.2012.
3. Smt. Rekha Rani, AD, CE'S Office, KGBO, CWC, Hyderabad along with soft copy for uploading the same in KGBO web site.
4. O/o The Superintending Engineer, Irrigation Circle, Dowlaiswaram, for wide publicity.
5. O/o The Executive Engineer, Investigation Division, Gandhipuram-3, N.W.D.A., Rajahmundry, for wide publicity.
6. O/o The Assistant Engineer, CPWD, Income Tax Office Complex, Rajahmundry for wide publicity.
7. The Junior Engineer, Site 46A, Koida for wide publicity.
8. O/o The Mandal Revenue Officer, Valerupadu, for wide publicity.
9. O/o The Mandal Revenue Officer, Rajahmundry, for wide publicity.
10. Notice Board.

Sub-Divisional Engineer