



No. LGSD-I / A-12 / 2013 – 14/
Government of India
Central Water Commission
Lower Godavari Sub Division No-I



Phone: 08743 233043
FAX: 08743 233043

H. No : 11-01-134
Opp. Sub Collector Office,
Bhadrachalam -507111.

Email: cwbcem@gmail.com

Date: 10.01.2014

NOTICE INVITING QUOTATIONS

Sealed quotations are invited on behalf of President of India from the registered Contractors/firms for the work of construction of one no. gate pillar at Sub Division office LGSD-I, CWC, Bhadrachalam, so as to reach this office by 15:00 hrs on 21.01.2014. The quotations will be opened by the undersigned on the same day at 16:00 hrs. Intended bidders or their authorized representative may present at the time of opening of quotation, if they wish so.

S. No	Description	Qty	Rate	Unit	Amount
1	Earth work excavation in foundation for pillar	0.486		Cum	
2	Laying of CC bed 1:2:4 in foundation for 10 cm thick and for hold fasts using 20 mm size stone aggregate in gate pillar	0.105		Cum	
3	Brick work with FPS bricks in foundation and plinth in Cement mortar 1:6				
a)	1st Footing below GL and 2 nd Footing	0.277		Cum	
b)	Brick masonry pillar	0.401		Cum	
4	12mm Cement plaster of mix 1:6 for pillar	5.340		Sqm	
5	Centring and shuttering including strutting propping etc., for gate	1.00		LS	
6	Finishing walls with water proofing cement paint of required shade	5.340		Sqm	

Terms & Conditions:

1. The sealed envelope contained quotations should be super scribed "Quotations for the work of Construction of one no. gate pillar at Sub Division office LGSD-I, CWC, Bhadrachalam" due for opening on 21.01.2014 at 16:00 hrs.
2. The rates quoted should be valid at least for a period of six months from the date of opening of the quotation.
3. Rates should be mentioned, inclusive of all taxes, levies, transportation, loading, unloading, and stacking of materials and providing necessary labour, materials, equipment, etc.
4. Security Deposit of 10% of final bill amount will be deducted and will be released after 6 months from the date of completion of the work.
5. All the debris and un-used materials etc. should be removed from the work site as soon as the work is completed. No extra charges will be paid for this purpose.

6. No T&P materials for any work including scaffolding/shuttering etc, will be provided by this department for the above said works.
7. The curing of the cement works should be done as per the standards by the contractor.
8. Materials to be used in the construction must be standard and approved ISI Code. The work should be standard and as per our description. The defective and sub-standard work is liable for rejection and same should be made good as per our requirement by contractor himself on his own expenditure, for which no extra payment will be made.
9. The work should be completed with in the 30 days of work order placed. No time extension will be given for completion of work until and unless beyond control of human beings.
10. The work will be inspected by the authorized representative of this Department and get himself be satisfied.
11. After satisfactory completion of the works in all respects, the bill in triplicate may be submitted for payment to the undersigned.
12. The payment will be made generally by Account Payee Demand draft on SBI, Red Hills, Hyderabad after completion of work satisfactorily and on submission of bill in triplicate.
13. However payment will be made on actual measurements only.
14. Income Tax 2.0%, (3% Educational Cess on IT) and Labour Cess 1% and other taxes, if any shall be deducted from the bill.
15. The Contractor must submit the proper Registration and Pan/Tan number.
16. This Department is not responsible for any accidents/losses to workers engaged in this work.
17. This office reserves the right to reject any one or all quotations without assigning any reasons thereof.



R N Ramesh Babu
SDE, LGSD-I, CWC, BCM

Copy for information to:-

1. The Superintending Engineer, Godavari Circle, CWC, Hyderabad along with soft copy for uploading the same in CPP.
2. The Executive Engineer, LGD, CWC, Hyderabad, w.r.t Lr. No. LGD/DB/Estimates/2013-14/ 3369 - 71, dated 10.12.2013.
3. Smt. Rekha Rani, AD, CE'S Office, KGBO, CWC, Hyderabad along with soft copy for uploading the same in KGBO web site.
4. O/o Sub Collector, Bhadrachalam for wide publicity.
5. O/o PO, ITDA, Bhadrachalam for wide publicity.
6. O/o Executive Engineer, Panchayat Raj Dept., Bhadrachalam for wide publicity.
7. Notice Board.



R N Ramesh Babu
SDE, LGSD-I, CWC, BCM

**SCHEDULE OF WORK FOR CONSRUCTION OF GATE PILLAR AT BHADRACHALAM UNDER
LGSD-I, CWC, BHADRACHALAM**

NAME OF WORK : Construction of One No. gate pillar at Sub Division Office

Place of Work: LGSD-I, CWC, Bhadrachalam

Estimated Amount: 6000 Rs.

Completion of Work : within 30 days from the commencement of the work

S.No	DESCRIPTION	Qty	Rate	Unit	Amount in fig.	Amount in words
1	Earth work excavation in foundation for pillar	0.486		Cum		
2	Laying of CC bed 1:2:4 in foundation for 10 cm thick and for hold fasts using 20 mm size stone aggregate in gate pillar	0.105		Cum		
3	Brick work with FPS bricks in foundation and plinth in Cement mortar 1:6					
	a) 1st Footing below GL and 2 nd Footing	0.277		Cum		
	b) brick masonry pillar	0.401		Cum		
4	12mm Cement plaster of mix 1:6 for pillar	5.340		Sqm		
5	Centring and shuttering including strutting propping etc., for gate	1.00		LS		
6	Finishing walls with water proofing cement paint of required shade	5.340		Sqm		
	SUB TOTAL					
	Income Tax 2% on Sub total					
	Educational Cess 3% on IT					
	Labour Cess 1% on Sub total					

We agree to carry out the work of "Construction of One no. Gate Pillar at Sub Division office, Bhadrachalam" under LGSD-I, CWC, Bhadrachalam as per NIQ for a total contract price of Rs..... (Amount in figures) (Rupees.....) (Amount in words) as per the terms and conditions of the contract.

Date:
Contractor

Signature of the