

No. LGSD-I / A-12 / 2013 – 14/ **Government of India Central Water Commission** Lower Godavari Sub Division No-I

H. No: 11-01-134 Opp. Sub Collector Office, Bhadrachalam -507111.

Date: 10.01.2014

Phone: 08743 233043 FAX: 08743 233043

Email: cwcbcm@gmail.com

NOTICE INVITING QUOTATIONS

Sealed quotations are invited on behalf of President of India from the registered Contractors/firms for the work of erection of gauge posts at site Kaleswaram under LGSD-I, CWC, Bhadrachalam, so as to reach this office by 15:00 hrs on 22.01.2014. The quotations will be opened by the undersigned on the same day at 16:00 hrs. Intended bidders or their authorized representative may present at the time of opening of quotation, if they wish so.

S. No	DESCRIPTION	Qty	Rate	Unit	Amount
1	Earth work in excavation by				
	mechanical means (Hydraulic				
	excavator) / manual means in				
	foundation trenches or drains (not				
	exceeding 1.5 m in width or 10 sqm				
	on plan), including dressing of sides				
	and ramming of bottoms lift up to				
	1.5 m, including getting out the				
	excavated soil and disposal of				
	surplus excavated soil as directed,				
	with in a lead of 50 m (for all kinds	0.640			
	of soil)	0.648		cum	
2	Supplying and filling in plinth with				
	local sand under floors including				
	watering, ramming consolidating				
	and dressing complete for	0.100			
	foundation in bed	0.108		cum	
3	Providing and laying cement				
	concrete above bed level up to plinth level with grade 1:2:4 (1 Cement: 2				
	Coarse Sand : 4 Graded stone agg 20				
	mm nominal size)	0.6370		cum	
	12mm Cement plaster of mix 1:6 for	0.0370		Cum	
4	pillar	1.7756		sqm	
		1.7750		3qiii	
	TOTAL				

Terms & Conditions:

- 1. The sealed envelope contained quotations should be super scribed "Quotations for the work of erection of gauge posts at site Kaleswaram under LGSD-I, CWC, Bhadrachalam" due for opening on 22.01.2014 at 16:00 hrs.
- 2. The rates quoted should be valid at least for a period of six months from the date of opening of the quotation.
- 3. Rates should be mentioned, inclusive of all taxes, levies, transportation, loading, unloading, and stacking of materials and providing necessary labour, materials, equipment, etc.

- 4. Security Deposit of 10% of final bill amount will be deducted and will be released after 6 months from the date of completion of the work.
- 5. All the debris and un-used materials etc. should be removed from the work site as soon as the work is completed. No extra charges will be paid for this purpose.
- 6. No T&P materials for any work including scaffolding/shuttering etc, will be provided by this department for the above said works.
- 7. The curing of the cement works should be done as per the standards by the contractor.
- 8. Materials to be used in the construction must be standard and approved ISI Code. The work should be standard and as per our description. The defective and sub-standard work is liable for rejection and same should be made good as per our requirement by contractor himself on his own expenditure, for which no extra payment will be made.
- The work should be completed with in the 30 days of work order placed. No time extension will be given for completion of work until and unless beyond control of human beings.
- 10. The work will be inspected by the authorized representative of this Department and get himself be satisfied.
- 11. After satisfactory completion of the works in all respects, the bill in triplicate may be submitted for payment to the undersigned.
- 12. The payment will be made generally by Account Payee Demand draft on SBI, Red Hills, Hyderabad after completion of work satisfactorily and on submission of bill in triplicate.
- 13. However payment will be made on actual measurements only.
- 14. Income Tax 2.0%, (3% Educational Cess on IT) and Labour Cess 1% and other taxes, if any shall be deducted from the bill.
- 15. The Contractor must submit the proper Registration and Pan/Tan number.
- 16. This Department is not responsible for any accidents/losses to workers engaged in this work.
- 17. This office reserves the right to reject any one or all quotations without assigning any reasons thereof.

R N Ramesh Babu SDE, LGSD-I, CWC, BCM

Copy for information to:-

- 1. The Superintending Engineer, Godavari Circle, CWC, Hyderabad along with soft copy for uploading the same in CPP.
- 2. The Executive Engineer, LGD, CWC, Hyderabad, w.r.t Lr. No. LGD/DB/Estimates/2013-14/3369 71, dated 10.12.2013.
- 3. Smt. Rekha Rani, AD, CE'S Office, KGBO, CWC, Hyderabad along with soft copy for uploading the same in KGBO web site.
- 4. O/o Sub Collector, Bhadrachalam for wide publicity.
- 5. O/o PO, ITDA, Bhadrachalam for wide publicity.
- 6. O/o Executive Engineer, Panchayat Raj Dept., Bhadrachalam for wide publicity.
- 7. Notice Board.



SCHEDULE OF WORK FOR ERECTION OF GAUGE POSTS AT SITE: KALESWARAM UNDER LGSD-I, CWC, BHADRACHALAM

NAME OF WORK: Erection of Gauge posts at site: Kaleswaram

Place of Work: Kaleswaram, Karimnagar Dist.

Estimated Amount: 10,000 Rs.

Completion of Work: within 30 days from the commencement of the work

S.No	DESCRIPTION	Qty	Rate	Unit	Amount in fig.	Amount in words
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, with in a lead of 50 m (for all kinds of soil)	0.648		cum		
2	Supplying and filling in plinth with local sand under floors including watering, ramming consolidating and dressing complete for foundation in bed	0.108		cum		
3	Providing and laying cement concrete above bed level up to plinth level with grade 1:2:4 (1 Cement: 2 Coarse Sand: 4 Graded stone agg 20 mm nominal size)	0.6370		cum		
4	12mm Cement plaster of mix 1:6 for pillar	1.7756		sqm		
	SUB TOTAL					
	Income Tax 2% on Sub total					
	Educational Cess 3% on IT					
	Labour Cess 1% on Sub total					

Date: Contractor Signature of the