



GOVERNMENT OF INDIA  
CENTRAL WATER COMMISSION  
INDRAVATI SUB-DIVISION  
KUMHARPARA  
Jagdalpur, Pin-494001

& : (07782) 228680 (O);  
☎ : (07782) 228680

NIQ No. ISD/A-6/ 2013-14/ 652-58

Dated 03.12.13

### Notice Inviting Quotations

Sealed quotations are hereby invited by the undersigned on behalf of the President of India for "laying of Cement Concrete road with CC interlocking paver blocks at ISD/Jagdalpur" from the approved and eligible contractors of CPWD/State Irrigation/PWD Departments. The quotations should reach in the office of the undersigned on or before at 11-12-2013 up to 1500 hrs and will be opened on the same day at 1530 hrs.


Sl. No.	Name of work and location	Estimated cost	Time allowed
1.	laying of Cement Concrete road with CC interlocking paver blocks at ISD/Jagdalpur (Schedule of Quantities enclosed)	Rs.3,00,000 (Rupees three lakhs only)	2 months

### Terms & Conditions:

1. The quotations duly signed should be properly sealed and dropped in quotation box in the office of the Sub divisional Engineer, Indravathi Sub- Division, Central Water Commission, Kumharpara, Jagdalpur-494001. The sealed envelop should be super scribed "laying of Cement Concrete road with CC interlocking paver blocks at ISD/Jagdalpur
2. In the event of opening of quotation being a holiday will be opened on the next working day with timings unchanged.
3. Quotationers must have PAN number and the copy of the same is to be submitted.
4. The undersigned does not bind him self to accept the lowest quotation and reserve the right to accept or reject any or all the quotations without assigning any reason thereof.
5. No tools and plants shall be issued to the contractor.
6. Before starting the work, material shall be got approved from SDE.
7. The time of completion shall be strictly adhered.
8. The date of start shall be reckoned from the day of date of issue of work order.
9. All materials required for the work are to be supplied by the contractor. The material must be ~~standard~~ quality and as per specifications and free from all defects. The

- material if found defective subsequently or not conforming to the specifications as stated above, have to be replaced by the firm without any additional charges. The work shall have a warranty period of minimum six months from the date of completion.
10. Before starting the work, material and colours of CC paver blocks shall be got approved from SDE,
  11. The quantity of work may be increased or decreased at the time of order without assigning any reason thereof.
  12. The rate quoted should be inclusive of all duties, taxes and other levies as applicable. No other incidental charge, whatsoever will be entertained.
  13. The validity of quotation for acceptance shall be 90 days and rates quoted should remain valid for 180 days from the date of opening.
  14. The rate should be quoted both in words and in figures. Correction/overwriting in the quotation if any shall be made by initialing, dating and re-writing.
  15. The payment will be made by Account payee cheque drawn on SBI, Red hills Branch, Hyderabad on production of pre-receipted bill in triplicate only after satisfactory completion of the work as per specifications.
  16. TDS shall be deducted from the bill at time of payment as per latest Govt. orders.
  17. The security Deposit @ 10% of bill amount will be deducted from the bill and will be released after 6 months from the date of completion of work and on satisfaction of the work done.

Encl: - Schedule of quantities

  
(K. Wilson Sala Kumar)  
Sub-divisional Engineer

Copy for information to:-

1. The superintending Engineer, Godavari Circle, CWC, Hyderabad with a request to arrange to publish the same in CPP portal.
2. The Deputy Director, O/o The Chief Engineer, KGBO, CWC, Hyderabad for updating the same in KGBO website.
3. Executive Engineer, Lower Godavari Division, CWC, Hyderabad for information.
4. The Sub Divisional Engineer, LGSD-1/Bhadrachalam
5. The Sub Divisional Engineer, LGSD-II /Rajahmundry
6. The AAO, Accounts Branch, LGD, CWC, Hyderabad.
7. Notice Board.

**Schedule Of Quantities**  
**NW :Laying of Cement Concrete road with CC Interlocking paver blocks at ISD/Jagdalpur Subdivision Office**

S.No	DESCRIPTION	Qty	Unit	Rate	Per	Amount in Figures	Amount in Words
1	Earth work excavation by mechanical means(Hydraulic Excavator)/manual means over areas (exceeding 30 cm in depth 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 50 m and lift upto 1.5 m disposed earth to be levelled and neatly dressed. All kinds of soil  Total Quantity	64.21	cum		cum		
2	Providing and laying 60 mm thick factory made cement interlocking paver block of M-30 grade made by block making machine with strong vibratory compaction of approved size design & shape laid in required colour and pattern over and including 50 mm thick compacted bed of coarse sand filling the joints with fine sand etc. all complete as per the direction of Engineer-in-charge.  Total Area	527.90	sqm		sqm		
3	Providing and laying at or near ground level factory made kerb stone of M-25 grade concrete in position to the required line, level and curvature, joined with cement mortar 1:3(1 cement 3 coarse sand), including making joints with or without grooves(thickness of joints except at sharp curve shall not to more then 5 mm), including making drainage opening where ever required complete etc. as per direction of Engineer-in-charge(length of finished kerb edging shall be measured for payment). (Precast C.C kerb stone shall be approved by Engineer-in-charge).  Total Quantity	1.566	cum				
	<b>Total Amount</b>						

Signature of the Contractor