



GOVERNMENT OF INDIA
CENTRAL WATER COMMISSION
INDRAVATHI SUB-DIVISION
KUMHARPARA
Jagdalpur, Pin-494001

& : (07782) 228680 (O),
☎ : (07782) 228680

NIQ No.ISD/A-12/ 2014-15/ 88-92

Dated 02.02.2015

Notice Inviting Quotations

Sealed quotations are hereby invited by the undersigned on behalf of the President of India for "Providing Balance Civil Works (Site installations) for new Site Talnar under ISD/Jagdalpur " from the approved and eligible contractors of CPWD/State Irrigation/PWD Departments and also from reputed Firms. The quotations should reach in the office of the undersigned on or before at **10-02-2015** up to 1500 hrs and will be opened on the same day at 1530 hrs.

Sl. No.	Name of work and location	Estimated cost	Time allowed
1.	Providing Balance Civil Works (Site installations) for new Site Talnar under ISD/Jagdalpur (Schedule of quantities enclosed)	Rs.2,76,000 (Rupees Two lakhs Seventy six thousands only)	30 days


Terms & Conditions:

1. The quotations duly signed should be properly sealed and dropped in quotation box in the office of the Sub divisional Engineer, Indravathi Sub- Division, Central Water Commission, Kumharpara, Jagdalpur-494001. The sealed envelop should be super scribed "**Providing Balance Civil Works (Site installations) for new Site Talnar under ISD/Jagdalpur .**
2. EMD of Rs.5600/- is to be furnished along with the quotations. The EMD of unsuccessful bidders will be returned as soon as the work awarded to the successful bidder.
3. In the event of opening of quotation being a holiday will be opened on the next working day with timings unchanged.
4. Quotationers must have PAN number and VAT registration and the copies of the same is to be submitted in addition to contractor registration copy.
5. The undersigned does not bind him self to accept the lowest quotation and reserve the right to accept or reject any or all the quotations without assigning any reason thereof.
6. No tools and plants shall be issued to the contractor.

o/c

7. Before starting the work, material/colours of paints shall be got approved from SDE.
8. The time of completion shall be strictly adhered.
9. In case the work is not commenced within 7 days from receipt of work order, the EMD will be forfeited to the President, Govt. of India and the contract will be cancelled.
10. The date of start shall be reckoned from the day of date of issue of work order.
11. All materials required for the work are to be supplied by the contractor. The material must be standard quality and as per specifications and free from all defects. material if found defective subsequently or not conforming to the specifications as stated above, have to be replaced by the firm without any additional charges. The work shall have a warranty period of minimum six months from the date of completion.
12. The quantity of work may be increased or decreased at the time of order without assigning any reason thereof.
13. The rate quoted should be inclusive of all duties, taxes and other levies as applicable. No other incidental charge, whatsoever will be entertained.
14. The validity of quotation for acceptance shall be 60 days and rates quoted should remain valid for 90 days from the date of opening.
15. The rate should be quoted both in words and in figures. Correction/overwriting in the quotation if any shall be made by initialing, dating and re-writing.
16. The payment will be made by DD or Account Payee cheque drawn on SBI ,Red hills Branch, Hyderabad on production of pre-receipted bill in triplicate only after satisfactory completion of the work as per specifications.
17. TDS shall be deducted from the bill at time of payment as per latest Govt. orders.
18. The security Deposit @ 10% of bill amount will be deducted from the bill and will be released after 6 months from the date of completion of work and on satisfaction of the work done.

Encl: - Schedule of quantities


(K. Wilson Sala Kumar)
Sub-divisional Engineer

Copy for information to:-

1. The superintending Engineer, Godavari Circle, CWC, Hyderabad with a request to upload the same in the CPP portal.
2. The Deputy Director, O/o The Chief Engineer, KGBO, CWC, Hyderabad for updating the same in KGBO website.
3. Executive Engineer, Lower Godavari Division, CWC, Hyderabad for information.
4. The AAO, Accounts Branch, LGD, CWC, Hyderabad.
5. Notice Board.

NAME OF WORK : Balance Civil Works (Site installations) for New Site Talnar

INDRAVATI SUB-DIVISION, JAGDALPUR

S.No	DESCRIPTION	Qty	Unit	Rate	Per	Amount
1	Clearing Jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth upto 30cm measured at a hight of 1 m above ground level and removal of rubbish up to a distance of 50m outside the periphery of the area cleared	4000	Sqm		100 Sqm	
2	Earth work Excavation by mechanical means(Hydraulic Excavator)/manual means over areas(exceeding 30 cm in depth 1.5m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 50 m and lift upto 1.5 m disposed earth to be levelled and neatly dressed in All kinds of soil for Gauge posts,Target poles and Direction poles	13.5	cum		cum	
3	Providing and laying CC in retaining walls, return walls, walls including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc. upto floor level, excluding the cost of centering, shuttering and finishing 1:2:4 (1 cement, 2 Coarse sand, 4 graded stone aggregate 20 mm nominal size) for Gauge posts,Target poles and Direction poles	1.35	cum		cum	
4	Fabrication and installation of guage posts at river banks including cost of civil works in foundation embedded in 1:2:4 RCC pedestal blocks of size 60 cmx60 cmx60 cm including the cost of steel reinforcements, centering, shuttering, finishing, reinforcement over the 1:4:8 CC base of size 80 cmx80 cmx15 cm with 12 mm thick plastering complete and marking the guage with synthetic enamel with standard metric gradation of 5 mm thickness in black & white alternatively & red synthetic enamel of 5 mm of width at every 100 mm etc complete. Reinforced cement concrete guage post of size 15 cmx10 cm (one side tapered in 5 cm length) made with 1:2:4 concrete mix 1.8 m long (U/s- 15 Nos., S/G - 15 Nos. and D/s - 15 Nos.)	45	no.		no.	
5	Providing and fixing of 3.6 mm thick 100 mm dia and 6 m length MS pipe (each weighing 59 kg) including cast and conveyance	4	no.		no	

NAME OF WORK : Balance Civil Works (Site installations) for New Site Talnar

INDRAVATI SUB-DIVISION, JAGDALPUR

S.No	DESCRIPTION	Qty	Unit	Rate	Per	Amount
6	Providing wood work in frames of doors, windows, clesrestry windows and other frames wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separaetly) Second class teak wood for target poles and direction poles	0.054	cum		cum	
7	Providing GI sheet to fix over wooden frames including cast and conveyance for target poles and direction boards	1.54	sqm		Sqm	
8	Painting with synthetic enamel paint of approved brand and manufacture of required colour to given an even shade Two or more coats on new work over and under coat of suitable shade with ordinary paint of approved brand and manufacture for target boards,direction boardrds, & wooden reepers	11.914	sqm		sqm	
9	Construction of MTBM					
9.1	Earth work Excavation by mechanical means(Hydraulic Excavator)/manual means over areas(exceeding 30 cm in depth 1.5m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 50 m and lift upto 1.5 m disposed earth to be levelled and neatlydressed All kinds of soil	2.017	cum		cum	
9.2	Providing and laying CC in position cement concrete of specified grade including cost of centering and shutterng - All work upto plinth level in CC 1:4:8 (1 cement, 4 Coarse sand,8 graded stone aggregate 40 mm nominal size)	2.017	cum		cum	
9.3	Brick work with common burnt clay F.P.S. (non modular)bricks of class designation 7.5 in foundation and plinth in Cement mortar 1:4	1.08	cum		cum	
9.4	Cement plaster in coarse sand of thickness 15 mm on rough side of single side or half brick wall of mix 1: 4	8.64	cum		cum	
9.5	finishing walls with Water proofing cement paint of required shade (two or more coats applied at 3.84 kg / 10 sqm	8.64	cum		cum	

NAME OF WORK : Balance Civil Works (Site installations) for New Site Talnar

INDRAVATI SUB-DIVISION, JAGDALPUR

S.No	DESCRIPTION	Qty	Unit	Rate	Per	Amount
9.6	Stone for MBM					
9.7	Sand filling for MBM					
10	Constrction of Segmentation blocks as directed by Engineer in charge	20	Nos		Nos	
	SUB TOTAL					
11	VAT @5% on Sub total					
	TOTAL		Rs.			