

Phone: 23308649  
Fax: 040- 23308652

Government of India  
Central Water Commission  
Lower Godavari Division

Krishna Godavari Bhavan  
11-4-648, 3<sup>rd</sup> floor  
A. C. Guards, Hyderabad

No. LGD/D-7/2012-13/H/ 1123-25

Dated 21 -04-2012

To

Sub: - Notice inviting quotation for Repairs and Renovation of telemetry room (328, KG Bhavan)-Reg

Sir,

Sealed quotations are invited for Repairs and Renovation of Telemetry Room (328, KG Bhavan).The sealed quotations should reach this office by 1430 Hrs. on 07-05-2012.The quotation will be opened on the same day at 15.00 Hrs. You are requested to be present yourself or sent your authorized representative to this office at the time of opening of quotations.

Sl. No	Description works	Unit	Quantity	Rate	Total Amount (In Rs.)		
					In Figures	In Words	
<b>As per Schedule Enclosed</b>							

**Terms & Conditions:**

- 1.The cover containing the quotations should be super scribed with quotation for "Repairs and Renovation of telemetry room " due for opening on 07 -05-2012 at 1500 hrs.
- 2.The income tax & other taxes as applicable shall be deducted from the total amount.
- 3.An EMD of 2% on quoted total amount shall be enclosed in the form of DD in favour of Executive Engineer, LGD, CWC, Hyderabad payable at Hyderabad. The EMD of unsuccessful bidder will be returned back immediately after finalization of bids. The EMD of the successful bidder will be released after completion of the contract/ renewal/ extended period. Any damage/penalty to the Govt. property it will be adjusted from the security deposit (EMD).
- 4.The quantity of work may increase or decrease as per necessity of work. Measurement may be done as par actual work done in the M Book. The amount will be paid for actual quantity of work recorded in the M Book.
- 5.The offer of rates kept open valid for a period of 60 days from the date of opening of the quotation.
- 6 After satisfactory completion of the works in all respects, the bill may be submitted in triplicate for payment to the undersigned.
- 7.The right to reject any quotation or all the quotations without assigning any reasons there off, rests with the undersigned.
8. Only those firms who are having proven experience in executing of the works and capable to complete the works in time need to quote their rates.
9. Necessary proof of PAN and TIN Number should be enclosed with the quotation.

Yours faithfully,

Executive Engineer

Copy for information to:-

1. The Superintending Engineer, Godavari Circle, CWC, Hyderabad.
2. The Accounts Branch, LGD, CWC, Hyderabad
3. Smt. K. Rekha Rani AD, O/o CE, KGBO for Keeping on KGBO web site.

**SCHEDULE OF WORK FOR REPAIRS AND RENOVATION OF TELEMETRY ROOM  
(328,KG BHAVAN)**

Sl. No	Description works	Unit	Quantity	Rate	Total Amount (In Rs.)	
					In Figures	In Words
1	2	3	4	5	6	7
1	Removal of existing damaged grid of false ceiling and electrical fixtures including disposal of debris to outside the premises and cleaning etc. complete as per the instruction of engineer in - charge	Sqm	59.46			
2	Polishing of Mosaic flooring with compressor	Sqm	59.46			
3	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade in two coats.	sqm	190.26			
4	Providing and fixing false ceiling with 12 mm thick plain/semi perforated or with design tiles of BWP type phenol formaldehyde synthetic resin bonded pressed particle board conforming to IS:3087 finished with a coat of aluminum primer on both sides & edges and two coats of synthetic enamel paint of approved quality on exposed face fixed to a grid made out of anodized aluminum (with 15 micron anodic coating) T-sections 35x15x1.5 mm size main runners and cross runners 23.5x19x1.5 mm fixed to main runners placed 600 mm centre to centre both ways so as to form a grid of 600 mm square. The frame work shall be suspended from ceiling by level adjusting hangers of 6 mm dia M.S. rod fixed to roof slab by means of ceiling cleats. The suspenders shall be placed 600x1200 mm centre to centre including fixing to the frame with C.P brace screws and applying a priming coat of zinc chromate yellow primer (aluminum frame work shall be paid separately).	sqm	59.46			

5	Providing and fixing aluminum work for doors, windows, ventilators and portions with extruded built up standard tubular sections/appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixed with rawl plugs and screws or with fixing clips, or with expansion hold fasteners including necessary filling up of gaps at junctions, at top, bottom and sides with required EPDM rubber/neoprene gasket etc. Aluminum sections shall be smooth, rust free, straight, mitered and jointed mechanically wherever required including cleat angle, Aluminum snap beading for glazing/paneling. C.P.brass/stainless steel screws all complete as per architectural drawing and the directions of Engineer -In Charge (Glazing and paneling to be paid for separately) for windows & ceiling frame work.					
	Polyester powder coated aluminum (minimum thickness of polyester powder coating 50 micron)	kg	30.00			
6	Providing and fixing glazing in aluminum door, window, ventilator shutters and partitions etc. with EPDM rubber /neoprene gasket of etc. complete as per the directions of engineer-in-charge.					
	With float glass panes of 5.50 mm thickness	sqm	4.830			
7	Cleaning of wood work with acid wash existing wood work like cupboards and cabins etc. complete	LS				
8	Labour charges for hand polish to existing wood work	LS				
	<b>Grand Total</b>					
	<b>Say</b>					

We agree to carry out the work "Repairs and Renovation of Telemetry Room (328,KG Bhavan)-as per NIQ for a total contract price of Rs..... (amount in figures) (Rupees ..... ) (Amount in words) as per the terms and conditions of the contract.

Date

Signature of Agency  
Name of the Authorized