



No. LGSD-II / AC- 24 / 2013 - 14/ 276-88
Government of India
Central Water Commission
Lower Godavari Sub Division No-II



Phone: 0883 2468753
FAX: 0883 2468753
Email: aecwc_rjy@yahoo.com

Opp. RTC Bus Complex,
Danavaiah Pet Post.
Rajahmundry -533 103.
Date: 23.12.2013

NOTICE INVITING QUOTATIONS

Sub: Quotation for the work of Erection of steel gate & Fencing on river side premises at Site Potteru, Malkangiri District, Odisha.

Sir(s)

Sealed quotations are invited on behalf of President of India for the work of "Erection of steel gate & Fencing on river side premises at site Potteru, Malkangiri District, Odisha", so as to reach this office by 15:30 hrs on 08.01.2014. The quotations will be opened by the undersigned on the same day at 16:00 hrs. Intended bidders or their authorized representative may present at the time of opening of quotation, if they wish so.

Sl.No.	Description of work	QTY.	RATE	UNIT	AMOUNT
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus soil as directed within a lead of 50m All kinds of soil. (Code2.8.1) Net Quantity	2.106		Cum	
2	Supplying and filling in plinth with local sand under floors including, watering, ramming consolidating and dressing complete. - For gate pillars (Code2.27) Net Quantity	0.162		Cum	
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work upto plinth level 1:3:6 (1 Cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) - For foundation bed concrete - For gate pillars (Code: 4.1.6) Net Quantity	0.324		Cum	
4	Brick work with F.P.S. bricks of class designation 75 in foundation and plinth in : Cement mortar 1:4 (1 cement : 4 coarse sand) - For 1 st footing - For gate pillars (Code: 6.1.1) Net Qty	0.504		Cum	
5	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor block 1:2:4 (1 Cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) (Code: 4.2.3) Net Quantity	0.729		Cum	
	Brick work with F.P.S. bricks of class designation 75 in superstructure above plinth level upto floor V level in all shapes and sizes in :				

