



No. LGSD-II / AC- 24 / 2013 - 14/ 1324-36
Government of India
Central Water Commission
Lower Godavari Sub Division No-II



Phone: 0883 2468753
FAX: 0883 2468753
Email: aecwc_rjy@yahoo.com

Opp. RTC Bus Complex,
Danavaiah Pet Post.
Rajahmundry -533 103.
Date: 23.12.2013

NOTICE INVITING QUOTATIONS

Sub: Providing Boat anchoring blocks at site 123, Potteru Malkangiri District, Odisha.

Sir(s)

Sealed quotations are invited on behalf of President of India for the work of "Providing Boat anchoring blocks at Site 123, Potteru Malkangiri District, Odisha", so as to reach this office by 15.30 hrs on 08.01.2014. The quotations will be opened by the undersigned on the same day at 16:00 hrs. Intended bidders or their authorized representative may present at the time of opening of quotation, if they wish so.

Sl.No.	Description of work	QTY.	RATE	UNIT	AMOUNT
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus soil as directed within a lead of 50m All kinds of soil. (code2.8.1) Net Quantity	3.200		Cum	
2	Supplying and filling in plinth with local sand under floors including, watering, ramming consolidating and dressing complete. (code2.27) Net Quantity	0.200		Cum	
3	Centering and shuttering including strutting, propping etc. and removal of form work for Foundations, footings, bases of Columns (Code: 4.3.1) Net Quantity	1.200		Sqm	
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth excluding the cost of centering and shuttering - All works up to plinth level 1:2:4 (1 Cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size)(Code: 4.1.4) Net Quantity	3.300		Cum	
5	CEMENT PLASTER (IN FINE SAND) 12 mm cement plaster of mix :1:4 (1 cement: 4 fine sand) (Code: 13.1.1) Net Quantity	3.200		Sqm	
6	Steel reinforcement for R.C.C. work including straightening, cutting bending, placing in position and binding all complete upto plinth level. Mild steel and Medium Tensile steel bars (Code:5.22.1) Net Quantity	59.920		Kg	
	Total				

