



No. LGSD-II / AC- 24 / 2013 - 14/300-1310  
Government of India  
Central Water Commission  
Lower Godavari Sub Division No-II



Phone: 0883 2468753  
FAX: 0883 2468753  
Email: aecwc\_rjy@yahoo.com

Opp. RTC Bus Complex,  
Danavaiah Pet Post.  
Rajahmundry -533 103.  
Date: 23.12.2013

**NOTICE INVITING QUOTATIONS**

**Sub: Shifting of Self Supporting Wireless mast at LGSD-II, Rajahmundry.**

Sir(s)

Sealed quotations are invited on behalf of President of India for the work of "Shifting of Self Supporting Wireless mast at LGSD-II, Rajahmundry", so as to reach this office by 15-30 hrs on 08.01.2014. The quotations will be opened by the undersigned on the same day at 16:00 hrs. Intended bidders or their authorized representative may present at the time of opening of quotation, if they wish so.

Sl.No.	Description of work	QTY.	RATE	UNIT	AMOUNT
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus soil as directed within a lead of 50m For foundation - All kinds of soil. (code2.8.1)	2.592		Cum	
2	Supplying and filling in plinth with local sand under floors including, watering, ramming consolidating and dressing complete. (code2.27)	0.432		Cum	
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work upto plinth level 1:2:4 (1 Cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) ( Code: 4.1.3)	2.304		Cum	
4	Providing holding down bolts of 100cm long with nuts & washers complete. 20 mm dia. holding down bolts (Code1221, Basic rates) Net Quantity	8.000		kg	
5	Centering and shuttering including strutting, propping etc. and removal of form work for Foundations, footings, bases of Columns ( Code: 4.3.1)	0.480		Sqm	
6	Labour charges for dismantling the existing mast and again re erecting at the new place on provided foundation, all the 5 pieces (each 3.00M.) in place as per the directions of the site-in charge including carriage charges of the mast pieces to the new place of erection.	L.S.		L.S	
	<b>Total</b>				

