



No. LGSD-I / A-12 / 2014 – 15/ 756 - 59
Government of India
Central Water Commission
Lower Godavari Sub Division No-I



Phone: 08743 233043
FAX: 08743 233043

H. No : 11-01-134
Opp. Sub Collector Office,
Bhadrachalam -507111.

Email: cwcbcm@gmail.com

Date: 14.07.2014

NOTICE INVITING QUOTATIONS


Sealed quotations are invited on behalf of President of India from the registered Contractors/firms for the "**Civil works for the Establishment of New Site Ankushapur under LGSD I, Bhadrachalam (Site installations)**" so as to reach this office by 15:00 hrs on 23.07.2014. The quotations will be opened by the undersigned on the same day at 16:00 hrs. Intended bidders or their authorized representative may present at the time of opening of quotation, if they wish so.

S. no	Description of work
1	Civil works for the Establishment of new site Ankushapur under LGSD-I, Bhadrachalam

Terms & Conditions:


1. The sealed envelope contained quotations should be super scribed "**Quotations for the civil works for the Establishment of new site Ankushapur under LGSD-I, CWC, Bhadrachalam**" due for opening on 23.07.2014 at 16:00 hrs.
2. The rates quoted should be valid at least for a period of six months from the date of opening of the quotation.
3. Rates should be mentioned, inclusive of all taxes, levies, transportation, loading, unloading, and stacking of materials and providing necessary labour, materials, equipment, etc.
4. Security Deposit of 10% of final bill amount will be deducted and will be released after 6 months from the date of completion of the work.
5. All the debris and un-used materials etc. should be removed from the work site as soon as the work is completed. No extra charges will be paid for this purpose.
6. No T&P materials for any work including scaffolding/shuttering etc, will be provided by this department for the above said works.
7. The curing of the cement works should be done as per the standards by the contractor.
8. Materials to be used in the construction must be standard and approved ISI Code. The work should be standard and as per our description. The defective and sub-standard work is liable for rejection and same should be made good as per our requirement by contractor himself on his own expenditure, for which no extra payment will be made.
9. The work should be completed within the 45 days of work order placed. No time extension will be given for completion of work until and unless beyond control of human beings.
10. The work will be inspected by the authorized representative of this Department and get himself be satisfied.
11. After satisfactory completion of the works in all respects, the bill in triplicate may be submitted for payment to the undersigned.
12. The payment will be made generally by Account Payee Demand draft on SBI, Red Hills, Hyderabad after completion of work satisfactorily and on submission of bill in triplicate.
13. However payment will be made on actual measurements only.
14. Income Tax 2.0%, (3% Educational Cess on IT) and Labour Cess 1% and other taxes, if any shall be deducted from the bill.
15. The Contractor must submit the proper Registration and Pan/Tan number.

16. This Department is not responsible for any accidents/losses to workers engaged in this work.
17. This office reserves the right to reject any one or all quotations without assigning any reasons thereof.


R N Ramesh Babu
SDE, LGSD-I, CWC, BCM

Copy for information to:-

1. The Superintending Engineer, Godavari Circle, CWC, Hyderabad along with soft copy for uploading the same in CPP.
2. The Executive Engineer, LGD, CWC, Hyderabad, w.r.t Lr. No. LGD/DB/Estimates/2014-15/1209-1211 dated 09.07.2014.
3. Smt. Rekha Rani, AD, CE'S Office, KGBO, CWC, Hyderabad along with soft copy for uploading the same in KGBO web site.
4. O/o Sub Collector, Bhadrachalam for wide publicity.
5. O/o PO, ITDA, Bhadrachalam for wide publicity.
6. O/o Executive Engineer, Panchayat Raj Dept., Bhadrachalam for wide publicity.
7. Notice Board.


R N Ramesh Babu
SDE, LGSD-I, CWC, BCM

**QUOTATAION FOR CIVIL WORKS FOR ESTABLISHMENT OF NEW SITE ANKUSHAPUR UNDER
LGSD-I, CWC, BHADRACHALAM**

NAME OF WORK : Civil works for establishment of new site Ankushapur under LGSD-I, CWC, Bhadrachalam

Place of Work : Ankushapur, Warangal Dist.

Completion of Work : within 45 days from the commencement of the work

S.No	DESCRIPTION	Qty	Rate	Unit	Amount	Amount in words
1	Clearing Jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth upto 30cm measured at a height of 1 m above ground level and removal of rubbish up to a distance of 50m outside the periphery of the area cleared	2000		Sqm		
2	Earth work Excavation by mechanical means(Hydraulic Excavator)/manual means over areas(exceeding 30 cm in depth 1.5m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 50 m and lift upto 1.5 m disposed earth to be leveled and neatly dressed All kinds of soil	7.83		cum		
3	Providing and laying CC in retaining walls, return walls, walls including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc. upto floor level, excluding the cost of centering, shuttering and finishing 1:2:4 (1 cement, 2 Coarse sand, 4 graded stone aggregate 20 mm nominal size)	1.350		cum		
4	Fabrication and installation of gauge posts at river banks including cost of civil works in foundation embedded in 1:2:4 RCC pedestal blocks of size 60 cmx60 cmx60 cm including the cost of steel reinforcements, centering, shuttering, finishing, reinforcement over the 1:4:8 CC base of size 80 cmx80 cmx15 cm with 12 mm thick plastering complete and marking the gauge with synthetic enamel with standard metric gradation of 5 mm thickness in black & white alternatively & red synthetic enamel of 5 mm of width at every 100 mm etc complete. Reinforced cement concrete gauge post of size 15 cmx10 cm (one side tapered in 5 cm length) made with 1:2:4 concrete mix 1.8 m long (U/s- 8 Nos., S/G - 8 Nos. and D/s - 8 Nos.)	24.000		no.		
5	Providing and fixing of 3.6 mm thick 100 mm dia and 6 m length MS pipe (each weighing 59 kg) including cast and conveyance item No. 7757 of DSR 2013	4.000		no.		

S.No	DESCRIPTION	Qty	Rate	Unit	Amount	Amount in words
6	Providing wood work in frames of doors, windows, clerestory windows and other frames wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately) Second class teak wood	0.0540		cum		
7	Providing GI sheet to fix over wooden frames including cast and conveyance	1.5375		sqm		
8	Painting with synthetic enamel paint of approved brand and manufacture of required colour to given an even shade Two or more coats on new work over and under coat of suitable shade with ordinary paint of approved brand and manufacture	11.9140		sqm		
9	Provision for construction of MTBM (Annexure-I)			LS		
10	Provision for construction of segmentation blocks			LS		
11	Laying of approach path to the site for a length of 100 m, width 1.5 m and thickness 15 cm with Moorum					
	i) Supply and stacking at site Moorum	22.500		cum		
	ii) Supplying, stacking and spreading 6 mm thick red bajri / Moorum, watering and rolling completely including preparation of the surface and rolling Item No. 16.6.1 With road roller/hand roller	150.000		sqm		
SUB TOTAL						

We agree to carry out the " **Civil works for the Establishment of new site Ankushapur under LGSD-I, CWC, Bhadrachalam**" as per NIQ for a total contract price of Rs.....
(Amount in figures) (Rupees.....) (Amount in words) as per the terms and conditions of the contract.

Date:

Signature of the Contractor

Quotation for Construction of Musto Type Bench Mark (MTBM)

Annexure-I

S.No	DESCRIPTION	QTY	UNIT	Rate	Amount	Amount in words
1	Earth work Excavation by mechanical means(Hydraulic Excavator)/manual means over areas(exceeding 30 cm in depth 1.5m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 50 m and lift upto 1.5 m disposed earth to be leveled and neatly dressed All kinds of soil (Item No 2.8.1 DSR 2013, page no 72)	2.017	cum			
2	Providing and laying CC in retaining walls, return walls, walls including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc. upto floor level, excluding the cost of centering, shuttering and finishing 1:2:4 (1 cement, 2 Coarse sand, 4 graded stone aggregate 20 mm nominal size) Code 4.2.3 DSR 2013 Foundation block for MTBM - Quantity as per above	2.017	cum			
3	Brick work with common burnt clay F.P.S. (non-modular) bricks of class designation 7.5 in foundation and plinth in cement mortar 1:4 (1 Cement : 4 Coarse Sand)(Item no. 6.1.1 of DSR-2013)	1.080	cum			
4	Cement Plaster in coarse sand of thickness 15 mm on rough side of single side or half brick wall of mix 1:4 (1 Cement : 4 Coarse Sand) (Item no. 13.5.1 of DSR-2013)	8.640	sqm	178.60	1543	
5	Finishing walls with water proofing cement paint of required shade Code 13.44.1 New work (two or more coats applied at 3.84 Kg/10 Sqm	8.640	sqm	54.4	470	
6	Stone for BM		LS			

Date:

Signature of the Contractor