



No. LGSD-II / AC- 24 / 2013 - 14/ 240-253
Government of India
Central Water Commission
Lower Godavari Sub-Division No-II



Phone: 0883 2468753
FAX: 0883 2468753
Email: aecwc_rjy@yahoo.com

Opp. RTC Bus Complex,
Danavaiah Pet Post,
Rajahmundry -533 103.
Date: 13 .02.2014

NOTICE INVITING QUOTATIONS

Sub: Construction of Compound wall around 3 sides of new office building at site 47,
Polavaram, West Godavari-District.

Sir(s)

Sealed quotations are invited on behalf of President of India from the registered contractors/
firms for the work of "Construction of Compound wall around 3 sides of new office building at site 47,
Polavaram, West Godavari-District", so as to reach this office by 15.30 hrs on 20.02.2014. The
quotations will be opened by the undersigned on the same day at 16.00 hrs. Intended bidders or their
authorized representative may present at the time of opening of quotation, if they wish so.

| Sl.No. | Description of work | QTY. | RATE | UNIT | AMOUNT |
|--------|---|---------------|------|-------|--------|
| 1 | Felling trees of the girth (measured at a height of 1 m above ground level), including cutting of trunks and branches, removing the roots and stacking of serviceable material and disposal of unserviceable material. Beyond 60 cm girth upto and including 120 cm girth. | 1 No. | | 1 No. | |
| 2 | Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 meters lead as per direction of Engineer - in - charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix) Concrete blocks of fencing angle posts | 0.486 Cum | | Cum | |
| 3 | Dismantling barbed wire or flexible wire rope in fencing including making rolls and stacking within 50 meters lead. | 47.275 Kg. | | Kg. | |
| 4 | Earth work in rough excavation, banking excavated earth in layers not exceeding 20 cm in depth, breaking clods, watering, rolling each layer with ½ tonne roller or wooden or steel rammers, and rolling every 3rd and top-most layer with power roller of minimum 8 tonnes and dressing up in embankments for roads, flood banks, marginal banks and guide banks or filling up ground depressions, lead upto 50 m and lift upto 1.5 m : All kinds of soil Compound wall West side & South side | 10.908 Cum | | Cum | |

Signature

| | | | | | |
|-----|---|----------------|--|------|--|
| 5 | Supplying and filling in plinth with local sand under floors including, watering, ramming consolidating and dressing complete. | | | | |
| | Compound wall West side & South side | 3.030 Cum | | Cum | |
| 6 | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size) Compound wall West side & South side | 1.818 Cum | | Cum | |
| 7 | Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand) | 4.141 Cum | | Cum | |
| 8. | Centering and shuttering including strutting, propping etc. and removal of form work for Foundations, footings, bases of Columns | 14.760 Sqm. | | Sqm. | |
| 9. | Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement :1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) for Plinth beam Compound wall complete . | 2.583 Cum | | Cum | |
| 10. | Steel reinforcement for R.C.C. work including straightening, cutting bending, placing in position and binding all complete upto plinth level. Mild steel and Medium Tensile steel bars 10mm Dia bars: 122.016 Kg. 6mm Dia Stirrups: 56.971 Kg. | 178.987 Kg. | | Kg. | |
| 11. | Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:6 (1 cement : 6 coarse sand) In superstructure | 16.127 Cum | | Cum | |
| 12 | 15 mm cement plaster on the rough side of single or half brick wall of mix : 1:6 (1 cement: 6 fine sand) | 169.746 Sqm | | Sqm | |
| 13 | Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works | 54.00Kg | | Kg. | |

Revised 19/7

| | | | | | |
|----|---|----------------|--|-----|--|
| 14 | Distemping with dry distemper of approved brand and manufacture (one or more coats) and of required shade on old work to give an even shade. | 169.746 Sqm | | Sqm | |
| 15 | Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work for Small gate | 0.900 Sqm | | Sqm | |
| 16 | Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m. | 3.636 Cum | | Cum | |

Terms & Conditions:-

1. The sealed envelope contained quotations should be super scribed "Construction of Compound wall around 3 sides of new office building at site 47, Polavaram, West Godavari-District."
2. An EMD of 2% on quoted total amount shall be enclosed in the form of Demand Draft in favor of Executive Engineer, Lower Godavari Division, CWC, Hyderabad payable at Hyderabad. The EMD of unsuccessful bidder will be returned back immediately after finalization of bids. The EMD of the successful bidder will be released on completion of the work in all respect.
3. 2% Income Tax & other taxes as applicable shall be deducted from the total amount.
4. The work will be carried out at Junior Engineer Site office, CWC, Polavaram, West Godavari-District, and will be inspected by the by the authorised representative of this Department and get himself be satisfied in all stages.
5. The Security Deposit of 10% may be deducted from the bill and will be released after six months completion of the work satisfactorily. If, any damage/penalty to the Government property, it will be adjusted from the security deposit.
6. The work should be completed with in 25 days of work order placed. No time extension will be given for completion of the work until and unless beyond the control of human beings.
7. Rates should be mentioned, inclusive of all taxes, levies, transportation, loading, unloading, and stacking of materials and providing necessary labour, materials, equipment etc.
8. The rates quoted should be valid at least for a period of six months from the date of opening of the quotation.
9. No T&P materials for any work including scaffolding/shuttering will be provided by this department for the above works.
10. The curing / watering work should be done as per the standards by the contractor.
11. After satisfactory completion of the work in all respects, bill in triplicate may be submitted for payment.
12. The payment will be made generally by Demand draft on SBI after completion of work satisfactorily and on submission of bill in triplicate.
13. However payment will be made on actual measurements only.
14. This Department is not responsible for any accidents / losses to the workers engaged in this work.
15. This office reserves the right to reject any one or all quotations without assigning any reasons there of.

To
M/s.


Sub-Divisional Engineer



Copy for information to:-

1. The Superintending Engineer, Godavari Circle, CWC, Hyderabad along with soft copy for uploading the same in CPP.
2. The Executive Engineer, Lower Godavari Division, CWC, Hyderabad, w.r.t Lr. No. LGD/DB/Estimates /2013-14/342-344, dated 12.02.2014.
3. Smt. Rekha Rani, AD, CE's Office, KGBO, CWC, Hyderabad along with soft copy for uploading the same in KGBO Web site.
4. O/o The Superintending Engineer, Irrigation Circle, Dowlaiswaram, for wide publicity.
5. O/o The Assistant Engineer, Investigation Sub-Division, N.W.D.A., Gandhipuram, Rajahmundry-3, for wide publicity.
6. O/o The Assistant Engineer, CPWD, Income Tax Office Complex, Rajahmundry for wide publicity.
7. O/o The Mandal Revenue Officer, Rajahmundry, for wide publicity.
8. O/o The Mandal Revenue Officer, Polavaram, West Godavari-District, for wide publicity.
9. The Junior Engineer, Site No.-47, CWC, Polavaram, for wide publicity.
10. Notice Board.

M. P. S.
12/2/14
Sub-Divisional Engineer

M. P. S.
12/2/14