



No. LGSD-II / AC- 24 / 2013 - 14/ 215-225
Government of India
Central Water Commission
Lower Godavari Sub Division No-II



Phone: 0883 2468753
FAX: 0883 2468753
Email: aecwc_rjy@yahoo.com

Opp. RTC Bus Complex,
Danavaiah Pet Post.
Rajahmundry -533 103.
Date: 13.02.2014

NOTICE INVITING QUOTATIONS

Sub: Improvement of office premises approach road at LGSD-II, Rajahmundry, East Godavari-District.

Sir(s)

Sealed quotations are invited on behalf of President of India from the registered contractors/ firms for the work of "Improvement of office premises approach road at LGSD-II, Rajahmundry, East Godavari-District.", so as to reach this office by 15.30 hrs on 20.02.2014. The quotations will be opened by the undersigned on the same day at 16.00 hrs. Intended bidders or their authorized representative may present at the time of opening of quotation, if they wish so.

Sl.No.	Description of work	QTY.	RATE	UNIT	AMOUNT
1	Surface dressing on old surface with hot bitumen of grade VG - 10 of approved quality using 1.95 kg of bitumen per sqm with 1.50 cum of stone chippings 11.2 mm nominal size per 100 sqm of road surface, including consolidation with road roller of 6 to 8 tonne capacity, etc. complete.	33.688 Sqm		Sqm	
2	Preparation and consolidation of sub grade with power road roller of 8 to 12 tonne capacity after excavating earth to an average of 22.5 cm depth, dressing to camber and consolidating with road roller including making good the undulations etc. and re-rolling the sub grade and disposal of surplus earth with lead upto 50 meters.	70.125 Sqm		Sqm	
3	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm) to wet mix macadam (WMM) specification including premixing the material with water at OMC in mechanical mix plant, carriage of mixed material by tipper to site, for all leads & lifts, laying in uniform layers with mechanical paver finisher in sub- base / base course on well prepared surface and compacting with vibratory roller of 8 to 10 tonne capacity to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge.	14.025 Cum		Cum	

4	2.5 cm premix carpet surfacing with 3 cum of stone chippings 10 mm nominal size per 100 sqm and bitumen emulsion (medium setting min. 65% bitumen contents) complying with IS : 8887, using 96 kg per cum of chippings of road surface, including consolidation with road roller etc complete .	346.250 Sqm		Sqm	
5	Providing and applying tack coat using bitumen emulsion conforming to IS: 8887, using emulsion pressure distributor including preparing the surface & cleaning with mechanical broom. With medium setting bitumen emulsion.				
	On old surface - On bituminous surface @ 0.25kg/sqm	276.125 Sqm		Sqm	
	On New surface - On W.B.M / W.M.M. @ 0.4kg/sqm	70.125 Sqm		Sqm	

Terms & Conditions:-

1. The sealed envelope contained quotations should be super scribed "Improvement of office premises approach road at LGSD-II, Rajahmundry, East Godavari-District."
2. An EMD of 2% on quoted total amount shall be enclosed in the form of Demand Draft in favor of Executive Engineer, Lower Godavari Division, CWC, Hyderabad payable at Hyderabad. The EMD of unsuccessful bidder will be returned back immediately after finalization of bids. The EMD of the successful bidder will be released on completion of the work in all respect.
3. 2% Income Tax & other taxes as applicable shall be deducted from the total amount.
4. The work will be carried out at Lower Godavari Sub Division No. - II Office, CWC, Rajahmundry, and will be inspected by the by the authorised representative of this Department and get himself be satisfied in all stages.
5. The Security Deposit of 10% may be deducted from the bill and will be released after six months completion of the work satisfactorily. If, any damage/penalty to the Government property, it will be adjusted from the security deposit.
6. The work should be completed with in 20 days of work order placed. No time extension will be given for completion of the work until and unless beyond the control of human beings.
7. Rates should be mentioned, inclusive of all taxes, levies, transportation, loading, unloading, and stacking of materials and providing necessary labour, materials, equipment etc.
8. The rates quoted should be valid at least for a period of six months from the date of opening of the quotation.
9. No T&P materials for any work including scaffolding/shuttering will be provided by this department for the above works.
10. The work should be done as per the standards by the contractor.
11. After satisfactory completion of the work in all respects, bill in triplicate may be submitted for payment.
12. The payment will be made generally by Demand draft on SBI after completion of work satisfactorily and on submission of bill in triplicate.
13. However payment will be made on actual measurements only.
14. This Department is not responsible for any accidents / losses to the workers engaged in this work.
15. This office reserves the right to reject any one or all quotations without assigning any reasons there of.

sdh
Sub-Divisional Engineer

To
M/s.

Copy for information to:-

1. The Superintending Engineer, Godavari Circle, CWC, Hyderabad along with soft copy for uploading the same in CPP.
2. The Executive Engineer, Lower Godavari Division, CWC, Hyderabad, w.r.t Lr. No. LGD / DB / Estimates/2013-14/342-344, dated 12.02.2014.
- ✓ 3. Smt. Rekha Rani, AD, CE's Office, KGBO, CWC, Hyderabad along with soft copy for uploading the same in KGBO Web site.
4. O/o The Superintending Engineer, Irrigation Circle, Dowlaiswaram, for wide publicity.
5. O/o The Assistant Engineer, Investigation Sub Division, Gandhipuram-3, N.W.D.A., Rajahmundry, for wide publicity.
6. O/o The Assistant Engineer, CPWD, Income Tax Office Complex, Rajahmundry for wide publicity.
7. O/o The Mandal Revenue Officer, Rajahmundry, for wide publicity.
8. Notice Board.


Sub-Divisional Engineer