

Schedule of Work

Name of Work: Repairs of floor and polishing of Mosaic flooring in some of the rooms of Krishna Godavari Bhavan, Central Water Commission, Hyderabad.

Sl.No	Description	Quantity	Unit	Rate in Rs.	Total Amount	
					In Figures	In words
1	Dismantling of stone slab flooring laid in cement mortar including stacking of serviceable material and disposal of unserviceable material within 50 m lead.	63.53	sq m			
2	Polishing of existing mosaic flooring using required cleaning material and cleaning the floor with water etc. complete.	1019.84	sq m			
3	Providing and laying vitrified floor tiles in different sizes with water absorptions less than 0.08% and conforming to IS : 15622 of approved make in all colours and shades, laid on 20 mm thick cement mortar 1 cement, 4 coarse sand including grouting the joints with white cement and matching pigments etc complete for size of tile 60cmx 60 cm	63.53	sq m			
4	Fixing vitrified floor tiles with cement based high polymer modified quickset adhesive (water based) conforming to IS; 15477, using 5 kg adhesive per sq m of tile area, in average 3 mm thickness	63.53	sq m			
	Total					