

दूरभाष : 040-2330 8650
फैक्स : 040-2330 8647

No.LKD/DB/NIT-NIQ/2010-11/3976-83

भारत सरकार
केन्द्रीय जल आयोग
निचली कृष्णा मंडल

11-4-648, ए सी गार्ड्स,
कृष्णा –गोदावरी भवन,
हैदराबाद -500 004.

दिनांक : 16.11, 2011

NOTICE INVITING QUOTATION

Sealed Quotations are invited For and on behalf of President of India from the Registered & Reputed Contractors for the following work as per the description of work supplied and the terms and conditions as mentioned below:

Description of work	Estimated cost	Last date for submission	Date for opening of Quotation
Construction of telemetry Tower at CWC site T. Ramapuram under LTSD, Kurnool	Rs.72,500 (including taxes)	25.11.11 1500 hrs	25.11.11 at 1530 hrs

TERMS AND CONDITIONS:

1. Sealed Quotations addressed to the Executive Engineer, Lower Krishna Division, CWC, “K.G. Bhawan” H.No.11-4-648, Room No.413, A.C. Guards, Hyderabad –500 004 (A.P.) should reach this office on or before 25.11.2011 by **1500** hrs. The quotations received will be opened on the same day at **1530** hrs in the presence of questioners or their representatives, if present.
2. The cover containing the quotation should be Superscribed as “**Construction of Telemetry tower at T.Ramapuram**”, due for opening on 25.11.2011 at **1530** hrs.
3. The quotation rates shall be remained valid up to 45 days.
4. Rates must be including all liabilities & taxes as applicable. No extra charges will be paid other than the rates approved.
5. Corrections & over writings shall be duly attested.
6. EMD @ 2 % of the Estimated amount of the work shall be enclosed in the form of demand draft (from Scheduled Bank) drawn in favour of the Executive Engineer, Lower Krishna Division, CWC, Hyderabad payable at Hyderabad. EMD of un-successful bidders will be returned back immediately after finalization of bids. The EMD of successful bidder will be released on completion of work in all respect.
7. Only those Contractors having experience related to this type of works and **able to complete the works within the given stipulated time only need to submit their Quotations.**
8. Successful Bidder need to submit the Security Deposit @ 10% of Quotation amount. Security Deposit will be released after 6 months from the date of completion of the work.

9. All the debris and un-used materials etc. should be removed from the work site as soon as the work is completed. No extra charges will be paid for this purpose.
10. Contractor should use his own men and materials. No Govt. property or staff allowed to use during the work in any case. Proper care should be taken not to damage any site installation etc. In case of any damages, necessary recovery for replacement/repair cost will be recovered from the contractor.
11. Materials to be used in the construction must be standard and approved ISI Code. The work should be standard and as per our description. The defective and sub-standard work is liable for rejection and same should be made good as per our requirement by contractor himself on his own expenditure, for which no extra payment will be made.
12. The work should be completed within the 20 days of Work Order placed. No time extension will be given for completion of work until and unless beyond control of human beings.
13. The work will be inspected by the authorized representative of this Department and get himself be satisfied.
14. After completion of work in all respect, bill may be submitted in triplicate alongwith advanced stamped money receipt for payment. Generally the payment will be made by Govt. Cheque payable at SBI, Red Hills Branch, Hyderabad.
15. 4% work tax, 2.3% (2% IT & 0.3% S.C) Income tax and 1% labour cess and other taxes, if any shall be deducted from the bill.
16. Right to reject any quotation or all the quotations without assigning any reason thereof, rests with the undersigned.
17. The Contractor must submit the proper **Registration and work permit, Pan/Tan number.**
18. This Department is not responsible for any accidents/losses to workers engaged in this work.
19. Employees of CWC and their relatives are not eligible for participating in the bid.
20. For details contact the Sub-divisional Engineer, MKSD-II, CWC, Kurnool.

Sd/-
(O.R.K.Reddy)
अधिषासी अभियंता
निचली कृष्णा मंडल

Copy forwarded for kind information to:

1. The Chief Engineer, KGBO, CWC, Hyderabad .
2. The S.M. Directorate, CWC, Room No.618, Sewa Bhawan, R.K.Puram, New Delhi-110066. (Quotation sent through e-mail to SM Dte. for hosting in CWC website)
3. The Superintending Engineer, K & C Circle, CWC, Hyderabad.
4. The Director, M&A,CWC, Hyderabad for hosting in KGBO web site
5. The Sub-divisional Engineer, LTSD, CWC, Kurnool for information & vide circulation.
6. AB, LKD, CWC, Hyderabad.
7. Jr. Engineer (HQ), LKD, CWC, Hyderabad for further action.
8. Notice Board

Sl.No.	Description	Quantity	Unit	Rate	Amount
1.	Earth work excavation for foundation by mechanical Means (hydraulic excavator)/ manual means over areas (exceeding 30cm in depth, 1.5m in width as well as 10 sqm on plan) including disposal of excavated earth, lead up to 50m and lift up to 1.5m, disposed earth to be levelled and neatly dressed Hard rock including Termination Block	4.814	Cum		
	b)Earth work excavation below 1.5m depth for Column	2.70	Cum		
2.	Supplying of 0.9mts dia C .C. rings including Cost and conveyance	4Nos	each		
3.	Providing and laying in position cement concrete of P.C.C. (1:4:8) bed in foundation excluding the costing of centering and shuttering -(4.1.8)	0.270	Cum		
4.	Providing and laying in position R.C.C. (1:3:6) for Termination block excluding the cost of centering, shuttering, finishing and reinforcement	0.764	Cum		
5.	Providing and laying in position R.C.C. (1:2.4) for column footing below ground level excluding the cost of centering, shuttering, finishing and reinforcement	1.08	Cum		
6.	Reinforced cement concrete work (1:1.5:3) for columns up to floor level excluding the cost of centering, shuttering, finishing and reinforcement	0.673	Cum		
	7.a) Centering and shuttering, propping etc., and removal of form for foundations, flooring bases of columns etc., for mass concrete.	6.664	Cum		
	b) centering above G.L. above 3m up to bottom of slab	1.36	Cum		
8.	Reinforced cement concrete work in beams, roof (slab) having slope up to 15 ^o excluding the cost of centering, shuttering, finishing and reinforcement with 1:2:4(Slab)	0.692	Cum		
9	Centering and shuttering, propping etc., and removal of form for suspended floors, roofs, landing and access platform	7.038	Sqm		
10.	Reinforcement for RCC work including straitening, cutting, bending, placing in position and binding all complete	140	kgs.		
11.	RCC work smooth finishing of the exposed surface with 6 mm thick cement mortar 1:3	16.0	sqm		

12. Stone boulders up to 200mm size refilling around the pillar in foundation up to G.L	4.91	Cum
13. Digging for laying of Bubbler conduit pipe	60	Rmt
14. G. I. Pipe 40mm dia medium quality	60	Rmt
15 Earthing Pits	2Nos.	Nos
16. Providing I or U Channel (about 2m length)	25	kgs
17. Providing and fixing rail of approved size by welding etc., to balcony railing including Applying a primer coat of approved steel primer 20mm dia medium wt steel tube Pipe (IS Code 1161:1998)	31.82	kgs