



कृ
11-4-648, ए.सी.गाड्स,
हैदराबाद - 500 004.
दिनांक 09-12-2014

सं. UGD/DB/Est.-7/2014-15/ 1699-1708

NOTICE INVITING QUOTATION

Sealed quotations are here by invited by the undersigned on behalf of the President of India for "Construction of Compound wall at Wireless Station Gangakhed under Purna Sub Division, CWC Nanded (MS)" from the approved and eligible contractors of CPWD/State PWD/State Irrigation Departments. The quotations should reach in the office of the undersigned on or before at 17- December-2014 up to 15.00hrs and will be opened on the same day i.e. 17-12-2014 at 15.30 hrs.

Sl.No.	Name of work & Location	Estimated Cost Rs	Earnest Money	Time allowed
1	Construction of Compound wall at Wireless Station Gangakhed Under Purna Sub Division, CWC.Nanded (MS).	3,19,990/-	6400/-	45 days


Terms & Conditions:

1. The quotations duly signed should be properly sealed and dropped in quotation box in the office of the Executive Engineer, Upper Godavari Division, Central Water Commission, Room No.316, H.No.11-4-648, KG Bhavan, AC Guards, Hyderabad-500004.The sealed envelope should be super scribed "Construction of Compound wall at Wireless Station Gangakhed Under Purna Sub Division, CWC.Nanded (MS)".
2. In the event of the date of opening of quotation being a holiday, quotations will be opened on the next working day with timings unchanged.
3. A bid security/ EMD of Rs.6,400/- (Rupees Six thousand four hundred only) shall be deposited in the form of an Account Payee Demand Draft/ Banker's Cheque from a scheduled bank in favour of "Executive Engineer, Upper Godavari Division, CWC, Hyderabad". The quotations not accompanied by EMD will not be considered. The EMD amount of the successful bidder will be forfeited if the bidder does not start the work within the prescribed period i.e., 10 days from the date of issue of work order.
4. Quotationers must have PAN/ TIN/ Service Tax Number/ VAT.
5. The undersigned does not bind himself to accept the lowest quotation and reserve the right to accept or reject any or all the quotations without assigning any reason thereof.

replaced by the firm without any additional charges.

7. The work shall have a warranty period of minimum six months from the date of completion.
8. Before starting the work, material shall be got approved from SDE, MSD, CWC, Nizamabad.
9. The quantity of work may be increased or decreased at the time of order without assigning any reason thereof.
10. The rate quoted should be inclusive of all duties, taxes and other levies as applicable. No other incidental charge, whatsoever will be entertained.
11. The validity of quotation for acceptance shall be 90 days and rates quoted should remain valid for 180 days from the date of opening.
12. The rate should be quoted both in words and in figures. Correction/ overwriting in the quotation, if any shall be made by initialing, dating and re-writing.
13. The payment will be made by Demand Draft on production of pre-receipted bill in triplicate only after satisfactory completion of work as per specification.
14. TDS shall be deducted from the bill at the time of payment as per latest Govt. orders.
15. The Security Deposit @ 10% of bill amount will be deducted from the bill and will be released after 6 (six) months from the date of completion of work and on satisfaction of the work done.

Encl: - Schedule of quantities.


(श्रीनिवासु बैरी)
अधिसासी अभियंता

Copy for information to:-

1. The Superintending Engineer, Godavari Circle, CWC, Hyderabad.
- ✓ 2. The Deputy Director, O/o the Chief Engineer, KGBO, CWC, Hyderabad for updating the same in KGBO Web site.
3. The Sub divisional Engineer / PSD/ CWC, Nanded for Information .
4. The Sub divisional Engineer/UGSD/MSD/ CWC, Aurangabad/Nizamabad for information.
5. The AAO, Accounts Branch, UGD, CWC, Hyderabad. The Expenditure may be incurred book by: **DWRIS (Plan)-Minor Works.**
6. The Site-in-charge, site Gangakhed.
7. Notice Board.

Name of Work: - Construction of Compound Wall around Site Office at Gangakhed

S.NO	Particulars	Quantity	Rate	Unit	Amount
1	Clearing the Site by cutting all the un wanted Trees & Bushes and leveling the Ground complete	L.S			
2	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50m. 2.8.1 All kinds of soil. (Code No.2.8.1)	34.200 Cum.			
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1-cement : 4 fine sand : 8 graded stone aggregate 40 mm nominal size) (Code No.4.1.9)	5.700 Cum			
4	Random rubble masonry with hard stone in foundation and plinth including leveling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) up to plinth level with :Cement mortar 1:6 (1 cement : 6 coarse sand) (Code No.7.1)	25.650 cum			
5	Brick work with common burnt clay F.P.S. (non modular)bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : 6.4.2 Cement mortar 1:6 (1 cement : 6 coarse sand) (Code No. 6.4.2)	27.324 cum			
6	12 mm cement plaster of mix : 13.1.2 1:6 (1 cement: 6 fine sand) (Code No. 13.1.2)	232.80sqm			
7	White washing with lime to give an even shade : 13.37.1 New work (three or more coats) (Code No. 13.37.1)	232.80sqm			
8	White washing with lime to give an even shade : 14.42.1 Old work (two or more coats) s (Code No. 14.42.1.)	342.00sqm			
.					