

फोन :040-23308651

फैक्स :040-23308648

भारत सरकार  
केन्द्रीय जल आयोग  
अधिरासी अभियंता कार्यालय  
उपरी गोदावरी मंडल

Govt. of India  
Central Water Commission  
Office of the Executive Engineer  
Upper Godavari Division



कू  
11-4-648, ए.सी.गाड्स,  
हैदराबाद - 500 004.

दिनांक : -11-2014.

सं. UGD/DB/Est.-7/2014-15/ 2014-16

17 NOV 2014

**NOTICE INVITING QUOTATION**

Sealed quotations are here by invited by the undersigned on behalf of the President of India for "Construction of Compound wall around site office at Saigaon under Manjeera Sub Division, CWC Nizamabad (TS)" from the approved and eligible contractors of CPWD/State PWD/State Irrigation Departments. The quotations should reach in the office of the undersigned on or before at 28-November-2014 up to 15.00hrs and will be opened on the same day i.e. 28-11-2014 at 15.30 hrs.


Sl.No.	Name of work & Location	Estimated Cost Rs	Earnest Money	Time allowed
1	Construction of Compound wall around site office at Saigaon Under Manjeera Sub Division, CWC.Nizamabad (TS).	4,06,312/-	8200/-	45 days

**Terms & Conditions:**

1. The quotations duly signed should be properly sealed and dropped in quotation box in the office of the Executive Engineer, Upper Godavari Division, Central Water Commission, Room No.316, H.No.11-4-648, KG Bhavan, AC Guards, Hyderabad-500004. The sealed envelope should be super scribed "Construction of Compound wall around site office at Saigaon Under Manjeera Sub Division, CWC.Nizamabad (TS)".
2. In the event of the date of opening of quotation being a holiday, quotations will be opened on the next working day with timings unchanged.
3. A bid security/ EMD of Rs.8,200/- (Rupees Seven thousand Five hundred only) shall be deposited in the form of an Account Payee Demand Draft/ Banker's Cheque from a scheduled bank in favour of "Executive Engineer, Upper Godavari Division, CWC, Hyderabad". The quotations not accompanied by EMD will not be considered. The EMD amount of the successful bidder will be forfeited if the bidder does not start the work within the prescribed period i.e., 10 days from the date of issue of work order.
4. Quotationers must have PAN/ TIN/ Service Tax Number/ VAT.
5. The undersigned does not bind himself to accept the lowest quotation and reserve the right to accept or reject any or all the quotations without assigning any reason thereof.

6. All materials required for the work are to be supplied by the contractor. The material must be standard quality and as per specifications and free from all defects. The material if found defective subsequently or not conforming to the specifications as stated above, have to be replaced by the firm without any additional charges.
7. The work shall have a warranty period of minimum six months from the date of completion.
8. Before starting the work, material shall be got approved from SDE, MSD, CWC, Nizamabad.
9. The quantity of work may be increased or decreased at the time of order without assigning any reason thereof.
10. The rate quoted should be inclusive of all duties, taxes and other levies as applicable. No other incidental charge, whatsoever will be entertained.
11. The validity of quotation for acceptance shall be 90 days and rates quoted should remain valid for 180 days from the date of opening.
12. The rate should be quoted both in words and in figures. Correction/ overwriting in the quotation, if any shall be made by initialing, dating and re-writing.
13. The payment will be made by Demand Draft on production of pre-receipted bill in triplicate only after satisfactory completion of work as per specification.
14. TDS shall be deducted from the bill at the time of payment as per latest Govt. orders.
15. The Security Deposit @ 10% of bill amount will be deducted from the bill and will be released after 6 (six) months from the date of completion of work and on satisfaction of the work done.

Encl: - Schedule of quantities.

  
(श्रीनिवासु बैरी)  
अधिसासी अभियंता

**Copy for information to:-**

1. The Superintending Engineer, Godavari Circle, CWC, Hyderabad.
- ✓ 2. The Deputy Director, O/o the Chief Engineer, KGBO, CWC, Hyderabad for updating the same in KGBO Web site.
3. The Sub divisional Engineer / MSD/ CWC, Nizamabad for Information along with the Technical Sanctioned Estimate.
4. The Sub divisional Engineer/UGSD/PSD/ CWC, Aurangabad/Nanded for information.
5. The AAO, Accounts Branch, UGD, CWC, Hyderabad. The Expenditure may be incurred book by: **DWRIS (Plan)-Minor Works**.
6. The Site-in-charge, GDSQ site Saigaon.
7. Notice Board.

Name of Work: - Construction of Compound Wall around Site Office at Saigon

S.NO	Particulars	Quantity	Rate	Unit	Amount
1	Earth work in rough excavation, banking excavated earth in layers not exceeding 20 cm in depth, breaking clods, watering, rolling each layer with ½ tone roller or wooden or steel rammers, and rolling every 3rd and top-most layer with power roller of minimum 8 tones and dressing up in embankments for roads, flood banks, marginal banks and guide banks or filling up ground depressions, lead up to 50 m and lift up to 1.5 m 2.2.1 All kinds of soil (Code No.2.2.1)	54.000 Cum.		Cum.	
2	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift up to 1.5 m. (Code No.2.25)	9.000 Cum.		Cum.	
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:3:6(1 Cement : 3 fine sand : 6 graded stone aggregate 40 mm nominal size) (Code No.4.1.7)	9.000 cum		cum	
4	Random rubble masonry with hard stone in foundation and plinth including leveling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) up to plinth level with :Cement mortar 1:6 (1 cement : 6 coarse sand) (Code No.7.1)	27.000 cum		Cum	
5	Random rubble masonry with hard stone in superstructure above plinth level and up to floor five level, including leveling up with cement concrete 1:6:12 (1 cement: 6 coarse sand: 12 graded stone aggregate 20 mm nominal size) at window sills, ceiling level and the like Cement mortar 1:6 (1 cement : 6 coarse sand) (Code No.7.2)	44.280 cum		Cum	
6	Fixing of existing Entrance gate 3mts.wide as per drawing to plumb to free movement (labor charges only)	1No.		---	
7	Pointing on stone work with cement mortar 1: 3(1 cement : 3 fine sand) :13.31.1 Flush / Ruled/ Struck or weathered pointing (Code No.13.33.1)	194.10 sqm		sqm	
				<b>Total</b>	